Sl. No.	Item grouped under sub-Heads and Sub-Works of the Estimate
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or i trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides c pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clod complete as per specifications.
2	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading an unloading from 0.00 to 10.00km
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and dow size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete la in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labou HOM of machinery, curing complete as per specifications.
4	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface suc as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labou complete as per specifications.
5	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20m and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixe concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level f roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, column piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor block plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as p specifications.
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in positio lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherev necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labou HOM of machinery complete as per specifications.
7	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering a finishing cutting etc., complete.
8	Covering Slab (As per Data Rate approved 100mm thick)
9	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfac including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand paperi including cost of materials, labour, complete as per specifications.
10	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos ceme sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all d dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.
	To

Certificate

1 Certified that the contractor has done the work Satisfactory and found Correct
2 Certified that the Contractor has removed all the debris from site.
3 Certified that there is no due from the contractor.
4 Certified that the contractor making own arrengments for men and materials